



Change is Good - A Story of Brine, Biology, Backwashing, and Bad Steel in Batavia

March 21, 2023



Stephen T. Dennison, PE
Senior Project Manager / Principal



Emily M. Conti, EI
Project Engineer



CITY OF
BATAVIA





Agenda

1. Project Overview
2. Backwashing
3. Brine
4. Bad Steel
5. Biology
6. Summary/Lessons Learned

PROJECT OVERVIEW



EXISTING SITE PLAN



NORTH BACKWASH
LAGOON

WELL #9

WTP #1

MIXING
TANK

WTP #2

GROUND STORAGE
TANK

SANITARY
LIFT STATION

NOTE: WELL #10 &
WELL #11
LOCATED ON
WENMOTH RD

SOUTH BACKWASH
LAGOON




Water Treatment Plants 1 and 2 Process Flow Diagram

Chemical Abbreviations	
CS	Chlorine Solution
FL	Fluoride
HMO	Hydrous Manganese Oxide
MnSO ₄	Manganese Sulfate
NaMnSO ₄	Sodium Permanganate
NaOCl	Sodium Hypochlorite
PO ₄	Blended Phosphate

Legend

Raw Water
 Partially Treated Water
 Finished Water
 Brine/NaOCl Solution
 Chemical Solution
 Backwash
 Lagoon Discharge





WATER TREATMENT PLANTS MODIFICATIONS PROJECT SCOPE

WTP #2 EXPANSION

Expansion of brine area for new brine equipment and salt storage area. Inclusion of new office space and additional bathroom.

DUALATORS

Rehabilitation of filtration equipment and replacement of media in two Dualators in WTP #1

BACKWASH STORAGE TANK

New underground backwash storage tank to replace open north backwash lagoon

HIGH SERVICE PUMPS

Rehabilitation of six high service pumps

WELLS NO. 9, 10 & 11

Rehabilitation of Deep Wells and pumping equipment

SODIUM HYPOCHLORITE FEED PUMPS

Replacement and relocation of feed pumps





Construction Overview

BIDDING/CONTRACTING

Awarded to Whittaker Construction &
Excavating, Inc. for \$4,411,037.48



SCHEDULE

Notice to Proceed: May 27, 2021
Substantial Completion: July 27, 2022
Final Completion: September 25, 2022
Contract Amendment Final Completion: June 2, 2023

FUNDING

IEPA SRF Loan
20 Year Term
1.35% Interest Rate





DEEP WELL AND HIGH SERVICE PUMP REHAB

- All equipment pulled and inspected
- All work phased to minimize disruption to operations
- Wells' motors reused and pumps replaced
- New level transducers for Wells
- Planned HSP motors' replacements



SODIUM HYPOCHLORITE PUMPS

- New pump skids installed in old brine area
- Replaced existing wall mounted pumps
- New skids provide better reliability and functionality





BACKWASHING

EXISTING BACKWASH LAGOON


- Radium-laden solid accumulation requiring periodic disposal as special waste
- Frequent high-volume washdowns of lagoon (average 1,300,000 gallons/year)
- Open to environment
- Safety concerns



PROPOSED UNDERGROUND BACKWASH TANK DESIGN GOALS:

- Prevent solid accumulation
- Improve operational efficiency
- Improve safety






PROPOSED SITE PLAN

UNDERGROUND
BACKWASH STORAGE
TANK

CONSTRUCTION CHALLENGE:
BACKWASH LAGOON TO REMAIN
OPERATIONAL DURING
CONSTRUCTION

BYPASS PUMP PLAN





Underground backwash storage tank during construction



New access hatch to access underground backwash tank



Sloped tank floor to prevent solids accumulation and to direct flow to effluent

Old lagoon filled in and site regraded and seeded over backwash tank





EXISTING BRINE AREA

- Brine tanks located in cramped room along with chlorine generators, sodium hypochlorite tanks, and misc. piping
- Very difficult for operators to load salt into brine tanks (safety concerns)
 - 8 pallets of salt, 49 bags per pallet loaded one bag at a time up a ladder into tanks
- No dedicated salt storage location



PROPOSED BRINE BUILDING ADDITION DESIGN:

- New brine tanks in recessed area
- Added salt storage space

SITE CHALLENGES

EXISTING SODIUM
HYPOCHLORITE ROOM

MAINTAIN ACCESS ROAD



LIFT STATION
TO REMAIN IN
CURRENT POSITION

IRON LAGOON

LIMITED SPACE



PROPOSED SITE PLAN





Completed Brine addition with relocated access road



Recessed brine tanks and brine piping, new tables for easy salt loading



New concrete loading dock and overhead access door

Interior salt storage space, new office, and new bathroom






BAD STEEL



DUALATOR FILTER VESSELS

- Original treatment plant for shallow wells to treat iron and manganese
- Converted to HMO system in mid-2000's for radium removal for deep wells
 - In service since early 90's



DUALATOR REHAB ANTICIPATION

- New concrete underdrain system
- Steel repairs in Detention Tank
- Coating system cleaning and overcoat
- Replacement of all valves and actuator system

DUALATOR DESIGN CHALLENGES

- Both tanks to remain completely operational during peak usage months
 - Only one tank offline at a time
- No previous rehab records
- Assumptions made for scope of repair because Dualators' interiors could not be inspected prior to construction



DUALATOR 2 CONDITION



Induced Draft Aerator

- Aerator trays in worse condition than expected and required replacement
- Aerator spray nozzles required replacement

Detention Tank - Floor

- Detention tank floor had severe pitting

Detention Tank – Misc.

- PVC vent lines damaged
- HMO feed piping and Detention Tank drain line to be replaced

DUALATOR 2 CONDITION



Tank Concrete Pad

- Concrete pad required minor repairs and sealing

Coating System

- Interior required full sandblasting and recoating
- Exterior required cleaning and topcoat

Filter Cells - Underdrain

- Underdrain required replacement and concrete fill (planned)



DUALATOR 2 CONDITION




Filter Cells - Troughs

- Welds failed on structural supports
- Welds failed on trough support components
- Pitting in trough steel
- New structural supports required for all troughs
 - Solution identified that did not require full trough replacements (cost savings)



DUALATOR VALVES

- Original System:
 - Pneumatic Valves
 - No Manual Operation Mode
 - Airlines Tied in Control Cabinet
 - Limited SCADA Capabilities
- New System:
 - Electric Actuated Valves
 - Manual Handwheel
 - Automated Display Cabinet
 - Added SCADA Capabilities





Fully recoated
aerator with new
nozzles and spray
trays




Fully recoated filter
cells with new trough
supports and
concrete underdrain
system

Fully recoated
detention tank with
new HMO piping,
drain valve, and
PVC vents



Fully recoated
exterior and all new
valves and actuators





BIOLOGY



Existing Filter Cell Media

- City identified that Filters removed ammonia from raw water
 - ~0.45 mg/L raw ammonia and no ammonia at effluent of Dualators
- BIOLOGICALLY ACTIVE FILTER
 - Nitrifying bacteria that oxidize ammonia in the filter media

Filter Operation Data

RAW AMMONIA
CONCENTRATION

0.45 mg/L

(9 ppm Chlorine
to treat 1 ppm
Ammonia)

CHLORINE
REQUIRED TO
REMOVE
AMMONIA

4.05 mg/L

TARGET FREE RESIDUAL -
EFFLUENT


1.05 - 1.10 mg/L

CHLORINE DEMAND IF NOT BIO ACTIVE

5.25 - 5.45 mg/L

ACTUAL CHLORINE DEMAND

1.05 - 1.10 mg/L




STRATEGY TO MAINTAIN BIOLOGY


- ~165 gallons of media pulled from each filter cell of each Dualator and stored in small tanks as seed media
 - Approx. 1/12 of total media
 - Total remaining media removed and disposed = 7,280 gallons
- Raw water pumped through storage tanks to keep media biologically active
- Existing media was used to re-seed new media with nitrifiers when installation occurred



Dualator 2 – Post Media Replacement



SUMMARY/ LESSONS LEARNED



SUMMARY / LESSONS LEARNED

BIOLOGY IS YOUR FRIEND

Recognize whether you have biologically active filtration, how to cultivate it for optimal treatment, and how to maintain it through construction activities

ASSUME THE WORST

If inspection of steel tank interior before construction is not possible, assume significant repairs required of aging components

SAFETY FIRST

Look for potential safety issues and opportunities for improvements

TEAMWORK

Coordination key to allow Operators to keep facilities operational during construction

PROACTIVITY SAVES

Proactively rehabilitate equipment to reduce potential for catastrophic failure and more costly repairs



THANK YOU

We value your time and appreciate the opportunity to present this afternoon.



Engineering
Enterprises, Inc.



STEPHEN T. DENNISON, PE
Senior Project Manager / Principal
sdennison@eeiweb.com
(630) 466-6762



EMILY M. CONTI, EI
Project Engineer
econti@eeiweb.com
(630) 466-6716



JEREMY BARKEI
Water and Sewer Utility Superintendent
City of Batavia

52 Wheeler Road
Sugar Grove, IL

www.eeiweb.com